

Stave Mechanics

Outline

1. Previous R&D
2. Near Term R&D
3. Questions/issues
4. Some current work
5. End Insertion
6. Schedule

*D. Lynn, BNL (with Yale, LBNL)
Santa Cruz, Aug 12, 2008*

Previous R&D--LBNL

Fabricated 5 stave prototypes

Lengths 1/3-1 meters

Narrow 7 cm width (was previous baseline)

Various tube sizes/shapes

Extensive FEA

Thermal modeling

Mechanical modeling

Measurement on Prototypes

IR Measurements (room temperature)

Stave deflection/sag

Thermal cycling

Previous R&D--Some Mechanical Conclusions

Stave Philosophy

Originally “stiff stave” with cantilevered space-frame support at each end.
Goal to minimize stave sag(must maximize stave design for stiffness)

Evolved to stave with multipoint support (to minimize sag) on cylinders.
(maximize design for thermal performance and minimal mass)

Flatness

Question remains on what spec should be on flatness (would be good to loosen this specification if it is not justified).

One stave achieved min-max < 200 um, rms~30 um

Flatness dependent upon uniformity of honeycomb thickness...must precision machine honeycomb if greater flatness required

Sag

Deflection of “non-stiff” staves less than 75 um if supported every 50 cm

Deflection agrees with FEA to within ~20%

Previous R&D--Some Thermal Conclusions

Cooling tubes

Not large difference between three options (in terms of $\Delta T/\text{watt}$)

1. Flattened tube in direct contact with facing
2. 4.8 mm tube in carbon foam (diamter for C_3F_8)
3. 2.8 mm tube in carbon foam (CO_2)

Coolant

CO_2 preferred to give more margin from thermal runaway

Facings

Not large difference in ply thickness (but ply orientation only briefly checked)



FEA

Agrees with measurements to $\sim 1\text{-}2^\circ\text{C}$, within uncertainties of material properties


Thermal Cycling

No change in thermal performance after 50 cycles from -35°C to 20°C

Recent Measurements on LBNL Stave at BNL









BNL Stave Measuring System Components



Short Stave
4.8 mm pipe
Heaters one side only
Silicon one side only




Stave Deformation Measurements



Deformation measurements – Differences


warm minus cold



These measurements done on side of stave without silicon or heaters

~ 300 μ m bow between room temperature and -30 C


warm minus cold



Not surprising as this stave was a thermal model, and so has silicon and heaters only on one side

Of more interest is change in bow between power on and power off. Change in bow is less than 15 μ m.

cold minus cold with power






Longitudinal coordinate [mm]

Deformation measurements – Differences

Repeatability Measurement on LBNL Stave

█ = warm
█ = cold, no power
█ = cold with power



Warm-to-warm and cold-to-cold repeatability is better than 20 μm

Cold-to-cold with power repeatability better than 30 μm

These measurements will be needed to be done with many more cycles with future staves, and results understood.

Near Term R&D Activities/Responsibilities

LBNL

Petal Prototyping

Foam/pipe shear studies (also relevant to pixels)

CO₂ cooling (working with SLAC)

Honeycomb for next generation of 11 cm wide staves (also for petals)

Expertise on stave mechanics

Yale

Foam/pipe shear studies

Foam machining

Tube R&D

Provide Foam-Tube units for next generation of 11cm wide staves

Thermal FEA

Near Term R&D Activities/Responsibilities

BNL

Assemble next generation of 11 cm wide staves

FEA-- Mechanical and Thermal

Deformation measurements (Room temp to -30C)

Thermal Imaging (down to -30C: NYU provides thermal imager)

End insertion with bracket prototyping

Other Institutions (US and non-US)

Much work to do.

How do we engage and organize?

Prototype Plan--Stave Variants

Note: Which staves to build still under discussion. One possible plan is presented. Uncertainties partly due to available materials

Short composites 0 and 00.

~ 35 cm long, 10.7 mm wide

5 mm and 3mm honeycomb (BNL 2pcf honeycomb or LBNL supplied honeycomb)

Purpose: Measure core properties, CTE, and CME

Short Staves 1 and 2

~ 35 cm long, 10.7 mm wide

5 mm and 3mm honeycomb (BNL 2pcf honeycomb or LBNL supplied honeycomb)

Existing (BNL) K13C2U 3-ply facings, 420 um thick, or other

5 mm CF side rails

Poco foam--stainless steel tubing assembly (Yale)

Purpose: Test assembly technique

Measure: Mechanical distortion, flatness, CTE, CME,
thermal performance under varying conditions of
temperature (25C to -30C), humidity, power, etc

Compare to FEA

Prototype Plan--Stave Variants

Short Staves 3 and 4 (if necessary), or...

Long (i.e. full length) stave 1.

Should have hopefully made decision on thickness

Should have preferred choice of facing material

Should have preferred choice of honeycomb

Should have end close-outs

Purpose: Last stave to be made before making full length stave for module mounting

Testing: Full round of testing and comparison to FEA as with short staves

Long stave 2.

Stave to be mounted with modules. Must satisfy requirements of the collaboration

Prototype Plan--Questions to be Answered and Issues (List not comprehensive)

Optimizations

Carbon Foam Type (Poco, Koppers, Other)

Carbon Foam Size (thermal performance vs mass)

Facing layup, orientation (stiffness vs thermal performance)

Honeycomb thickness, density (stiffness)

Machining

How much thicker does carbon foam have to be than tube?

Can we grind 1.2 m honeycomb to < 50 um flatness

Support

Are CF tubes for side rails sufficient with various end-insertion concepts?

Is carbon dust generated during inserstion? Is this a concern

Stainless Steel Tubes

Is electrical isolation required? Corrosion issues? (From electrical standpoint, I don't think isolation is required).

Prototype Plan--Questions to be Answered & Issues(Con't)

Stiffness

What now drives stiffness requirement? Sag is minimized via supports
Does end insertion drive stiffness requirement?

Stability

Need FEA frequency analysis, eventually coupled to support
Measure stability with accelerometers with next generation stave? What
use as excitation?

Glues

Se4445 have any impact on detector performance (before and after irradiation)
Glue for bus cable, glue for honeycomb-facing
Tube-foam glue
Gluing on silicon question

Assembly technique

Need to refine assembly technique. Must be transferable to large scale
production.

Some Current Work--LBNL


LBNL Working to Answer Question of Reliability of Tube-Foam Interface

Shear Stress Samples

- Made 5mmx5mmx6cm foam/Al tube samples to thermal cycle and look for foam cracks visually at the moment. This is for both POCO and a candidate pixel foam. Curing. Results next week.




| Sample | Priority | Tube Type | Foam Type | Tube/Foam Adh | Foam/Facing Adh | Facing |
|--------|----------|----------------|-----------|---------------|-----------------|--------------------|
| A | 7 | Al (2.85mm OD) | POCO | CGL | 9396/30%BN | 90 -0-0 -90 K13D2U |
| B | 1 | Al (2.85mm OD) | POCO | EG7658 | 9396/30%BN | 90 -0-0 -90 K13D2U |
| C | 3 | Al (2.85mm OD) | POCO | 9396/30%BN | 9396/30%BN | 90 -0-0 -90 K13D2U |
| D | 6 | Al (2.85mm OD) | Allcomp2 | CGL | 9396/30%BN | 90 -0-0 -90 K13D2U |
| E | 2 | Al (2.85mm OD) | Allcomp2 | EG7658 | 9396/30%BN | 90 -0-0 -90 K13D2U |
| F | 4 | Al (2.85mm OD) | Allcomp2 | 9396/30%BN | 9396/30%BN | 90 -0-0 -90 K13D2U |



Some Current Work--Yale

Graphite Foam


- Samples procured from two sources:
 - Poco
 - Koppers
- Poco has much more uniform porosity
- Both machine easily...however, Koppers is very fragile due to pore size variability.




Some Current Work--Yale

Tubing R&D

- Tubing samples procured from two sources:
 - Small Parts Inc (seamed and drawn) 2.76 mm OD x 2.16 mm ID
 - McMaster Carr
- Tube bending fixture developed and in use
- Two sources for <3 meter lengths identified:
 - Superior Tube (Thanks, David Lynn...)
 - New England Small Tube
- Next step: order tubing lengths sufficient for prototype



Some Current Work--Yale



Prototype Stave Thermal Mode

0.3 watts/chip, $T_{\text{tube wall}}$ held at 240 °K
-Top View

- As a starting point, I attempted to duplicate results from M. Cepeda et al. [Mechanical and Cooling Design Studies for an Integrated Stave Concept for Silicon Strip Detectors for the Super LHC](#), 18 June 2008.
- Specifically, I looked at the model presented on p.17.
- Modeled $\frac{1}{4}$ of stave cross-section using CosmosWorks
- Maintained tube inner wall at -35°C
- 0.3 watt generated at each of five chips
- Used conductivity information from table 5 of study
- Result: temperature rise at detector surface of 13°C vs 8°C from fig.20
- No obvious modeling or mat'l property errors at this point, but still looking...
- I'm currently developing a simple SINDA (finite differencing) model to check my results.
- Next: simple two-phase thermo-fluid model of tube
- After that: full-scale thermo-fluid model of current design


Some Current Work – BNL

Last Aluminum Honeycomb Stave Prototype Before Attempting All CF Prototype

Purpose:



Refine assembly technique

Use for end-insertion tests






Some Current Work – BNL

AI stave thickness uniform to min-max=4 thousands



Some Current Work – BNL

Stave flatness rms=30 μm , Min-Max=215 μm



End Insertion Bracket

Recently prototyped in thermoplastic one version of bracket (lacked sufficient stiffness)


Version below is being designed for sufficient stiffness in thermoplastic (Gordeev). Will be used with existing long stave at BNL

Like to prototype in carbon fiber for long stave 1




End Insertion Installation

JUMPER BASED ID BARREL SUPPORT STRUCTURE AND FRONT STAVE INSTALLATION PROCEDURE (PROPOSAL)



End Insertion Installation

Installation Carriage



Stave Prototyping--Schedule

| | | |
|------------|---------------------------|---|
| Sept 08 | Composite Staves 0 and 00 | |
| Oct Nov 08 | Short Staves 1-2 | Need dummy silicon, bus cable, heaters |
| Mar-Apr 09 | Long Stave 1 | Need preferred facings, closeouts-end insertion |
| Aug 09 | Long Stave 2 | Could be used with real modules |

Above schedule is my own first pass and needs discussion, agreement.

Note that in Allport's MIWG schedule, a short stave is fabricated by Jan 09, and a long stave suitable for module mounting is ready in May 2010.