

**Report From  
The International Linear Collider  
Technical Review Committee**

**Gregory A. Loew**

**Santa Cruz Linear Collider Retreat  
UC Santa Cruz**

**June 26-29, 2002**

## Talk Outline

- You have had two elaborate LC technical talks (G. Dugan and H. Weise)
- This talk will not present technical conclusions
- Emphasis today is on the TRC process, progress and prospects
- TRC Charge
- Structure and responsibilities of the Committee
- Milestones to date
- Contents
- Big issues
- Future milestones

# SECOND ILC-TRC CHARGE

- To assess the present technical status of the four LC designs at hand, and their potentials for meeting the advertised parameters at 500 GeV c.m. Use common criteria, definitions, computer codes, etc., for the assessments.
- To assess the potential of each design for reaching higher energies above 500 GeV c.m.
- To establish, for each design, the R&D work that remains to be done in the next few years.
- To suggest future areas of collaboration

## **Steering Committee**

**Chair:** Gregory Loew

**Members:** 1) Reinhard Brinkmann (DESY)  
2) Kaoru Yokoya (KEK)  
3) Tor Raubenheimer (SLAC)  
4) Gilbert Guignard

## **Working Groups**

Technology, RF and Energy Performance

**Chair:** Daniel Boussard

Luminosity Performance

**Chair:** Gerry Dugan

## **The Four Technical LC Approaches to be Assessed**

- 1) TESLA
- 2) JLC (C-band)
- 3) JLC (X-band)/NLC (X-band)
- 4) CLIC

# **Second ILC-TRC Report**

## **Major Milestones to Date**

- |                            |  |
|----------------------------|--|
| <b>February 8-9, 2001</b>  | ICFA at its DESY meeting requests second ILC-TRC study and report  |
| <b>July 27, 2001</b>       | After several months of work and discussions, ILC-TRC Steering Committee is formed, and new proposal is submitted to ICFA in Rome.<br>ICFA accepts proposal. |
| <b>August-October 2001</b> | Constitution of the Working Groups   |
| <b>February 4-8, 2002</b>  | First review and discussion of Working Group reports at LC 2002 (SLAC)   |
| <b>April 10-12, 2002</b>   | Second review (CERN)   |
| <b>June 7-9, 2002</b>      | Third review following EPAC (Paris)  |

# ILC-TRC REPORT

## TABLE OF CONTENTS

0. Executive Summary
1. Charge, Plans and Membership
2. The Megatables
3. Descriptions of the Four Machines at 500 GeV cm
4. Upgrade Paths to Higher Energies
5. Test Facilities and Other Project R&D Programs
  - a) Descriptions of Existing Test Facilities
  - b) Planned project R&D at Test Facilities and other R&D efforts [indicating dates to completion]
6. Technology, RF and Energy Working Group Assessments
7. Luminosity Performance Working Group Assessments
8. Reliability and Availability
9. Summaries of R&D work that remains to be done
  - a) For individual machines
  - b) By inter-machine collaborations

Table 1.1 Overall Parameters

	TESLA			JLC (C)			JLC/NLC* (X)			CLIC	
	500 GeV	800 GeV	500 GeV	500 GeV	1000 GeV	500 GeV	1000 GeV	500 GeV	1000 GeV	500 GeV	3000 GeV
Center of mass energy	500 GeV	800 GeV	500 GeV	5.7	5.7/11.4 <sup>†</sup>	500 GeV	1000 GeV	500 GeV	1000 GeV	500 GeV	3000 GeV
RF frequency of main linac (GHz)	1.3								11.4		30
Design luminosity ( $10^{33} \text{ cm}^{-2} \text{ s}^{-1}$ )	34.0	58.0	16.8	25.0	25.0	25.0 (20.0)	25.0 (30.0)	14.1	25.0 (30.0)	14.1	100.0
Linac repetition rate (Hz)	5	4		100		150 (120)	100 (120)	200	100 (120)	200	100
No. of particles/bunch at IP ( $10^{10}$ )	* 2	1.4		0.75					0.75		0.4
No. of bunches/pulse	2520	4986		192					192		154
Bunch separation (nsec)	337	176		1.4					1.4		0.67
Bunch train length (µsec)	950	860		0.267					0.267		0.102
Beam power/beam (MW)	11.3	17.5	5.8	11.5		8.7 (6.9)	11.5 (13.8)	4.9	8.7 (6.9)	11.5 (13.8)	14.8
Unloaded/loaded gradient <sup>‡</sup> (MV/m)	23.4 / 23.4	35 / 35	41.8/31.5	41.8/31.5 / 70/54		70 / 54			70 / 54		172 / 150
Total two-linac length (km)	30	30	17.1	29.2		12.6	25.8	5.0	12.6	25.8	27.5
Total beam delivery length (km)	3			3.7					3.7		5
Proposed site length (km)	33			33					32		40
Total site AC power <sup>§</sup> (MW)	140	200	235	310		215 (185)	280 (320)	XX	215 (185)	280 (320)	XX
Tunnel configuration <sup>¶</sup>		Single		Separate		Separate	Separate	Two-Beam	Separate	Separate	Two-Beam

\* Numbers in ( ) for the JLC/NLC correspond to US site with 120 Hz repetition rate.

† The 1 TeV JLC-C collider uses a C-band rf system for the first 200 GeV of each linac followed by an X-band rf system for the remaining 300 GeV of acceleration - the X-band rf system would be identical to that described for the JLC-X band collider.

‡ The main linac loaded gradient includes the effect of single-bunch (all modes) and multibunch beam loading, assuming that the bunches ride on crest. Beam loading is based on bunch charges in the linacs, which are slightly higher than at the IP.

§ Total site power includes AC for linac rf and cooling systems as well as power for all other beam lines and site facilities except for the JLC-C case where the AC power only includes that for the main linac rf generation.

¶ The single tunnel layout has both the klystrons and accelerator structures in the main linac tunnel while the separate tunnel layout places the klystrons and modulators in a separate enclosure. The Two-Beam scheme uses the separate tunnel layout for the drive linac - there are no klystrons and modulators associated with the main linac.




Figure 2: Sketch of the overall layout of TESLA.












Figure 3: Sketch of the 5 m diameter TESLA linac tunnel.

# Phase-I R&D Summary

C-band Klystron	Klystron Modulator	RF Pulse Compressor	Accelerating Structure
50 MW, <sup>OK</sup> 2.5 sec, 47 % Life test >5000 hour, OK.	110 MW <sup>OK</sup> 100 pps Smart modulator using inverter HV charger. Running for klystron life test.	Flat Pulse Gain 3.3 Three-cell cavity.	1.8 m <sup>OK</sup> Choke-Mode Beam acceleration at 50 MV/m was done at ATF-KEK, with S-band model. HOM damping performance was provided by ASSET-SLAC test, 1998.
		 	



# The NLC Configuration




NLC - The Next Linear Collider Project

# NLC Main Linac RF System



Induction Modulator NLC 8-Pack




- Low Level RF System
- One 490 kV 3-Turn Induction Modulator
- Eight 2 KW TWT Klystron Drivers (not shown)
- Eight 75 MW PPM Klystrons
- Delay Line Distribution System (2 Mode, 4 Lines)
- Eight Accelerator Structure Sextets

NLC "Single Feed"  
(5.4 m of Accelerator)

Single Mode Extractor

Klystron RF Pulse  
75 MW, 3168 ns  
**600 MW**  
2 Mode Launcher




58.6 m

Beam Direction →

Six 0.9 m Accelerator Structures  
(85 MW, 396 ns Input Each)

**GOAL 70 MV/m (UNLOADED)**





**OVERALL LAYOUT OF THE CLIC COMPLEX AT 500 GeV C.M.**

[Welcome](#) | [Table of Contents](#) | [Publications](#) | [Minutes](#) |

stn February 2001

<http://cern.web.cern.ch/CERN/Divisions/PS/CLIC/Layout/CLIC500.html>

## **Test Facilities, etc.**

<b>TTF I</b>	2 modules (16 9-cell structures) ~ 25 MV/m Test of superstructure this September Tests conclude in Fall 2002  Electropolished 9-cell structure reaches 35 MV/m (March 2002)
<b>TTF II</b>	Commissioning starts summer 2003
<b>C-Band</b>	Tests proceed at KEK and towards FEL construction at SPRING-8 (next three years)
<b>ATF (KEK)</b>	DR testing for next three years
<b>NLCTA (SLAC)</b>	X-Band structure tests and 8-pack tests continue for next three years
<b>ASSET</b>	Ongoing collimator and structure tests
<b>CTF-2</b>	Ends operation in Fall 2002
<b>CTF-3</b>	Tests will start in late 2004 and continue for 3-4 years

# TESLA TEST FACILITY (HALL 3)






Figure 1: Layout of the TESLA test Facility at DESY.










# Overall Layouts

## CLIC Test Facility CTF3



## TRC Working Group Members

<b>Technology, RF Power &amp; Energy Performance Group</b>	<b>Luminosity Performance Group</b>
<b>Daniel Boussard</b>	<b>Gerry Dugan</b>
Adolphsen, Chris	Assmann, Ralph
Braun, Hans H.	Decking, Winfried
Chin, YongHo	Gareyte, Jacques
Edwards, Helen	Kozanecki, Witold
Hübner, Kurt	Kubo, Kiyoshi
Lilje, Lutz	Phinney, Nan
Logatchov, Pavel	Rogers, Joe
Pasquinelli, Ralph	Schulte, Daniel
Ross, Marc	Seryi, Andrei
Shintake, Tsumoru	Settles, Ronald
Toge, Nobu	Tenenbaum, Peter
Weise, Hans	Wolski, Andy
Wilson, Perry	Walker, Nick

# **Technology, RF Power and Energy Working Group**

## **(D. Boussard)**

### **Sub-group 1** (*P. Wilson*)

Accelerator Structures

### **Sub-group 2** (*Y.H. Chin*)

Power Sources  
(Klystrons, Power Supplies, Modulators  
and Low Level RF)

### **Sub-group 3** (*K. Hübner*)


Power Distribution  
(RF Pulse Compression, Waveguides,  
Two-beam)

### **Sub-group 4** (*W. Decking & H. Weise*)

Injectors, Damping Rings and Beam Delivery

### **Sub-group 5** (*R. Pasquinelli*)

Reliability and Availability





# HOM-Free Linear Accelerating Structure


C-band L

Cooling water channel

HOM Absorbers (SiC)

Wake Field

\*Choke-Mode Cavity  
T. Shintake 1992



150 mm

$\lambda/4$

$\lambda/4$

BEAM



Spacer Ring

Copper Disks





Choke Filter

Trapped Accelerati Mode

# Pitting on Cell Irises of a 1.8 m Structure After Operation at Gradients up to 50 MV/m



# Explosive Electron Emission




12-88

6110A5

SECRET (U) (S)

# T53VG3RA Input Coupler


---



Juwen Wang



# PIE-shaped Slot – rounded cell






NLC - The Next Linear Collider Project

# PPM Focused X-Band Klystron

Periodic Permanent Magnet (PPM) Focused  
X-Band (11.4 GHz) Klystron



D. L. Burke

NLC Report  
April 2000


# 8-Pack Phase-I (SLED-II System)

2 Klystrons each with  
75 MW for >2.4  $\mu$ secs

Cross-Potent  
(Cold Test Model)




Dual-Mode  
SLED-II



Completed at the end of  
calendar 2002 to  
demonstrate dual-mode  
capability and test DLDS  
components in 2003.

“Single-Feed”  
600 MW for 400 nsec



600 MW  
400 ms

# Luminosity Performance Working Group (G. Dugan)

## **Sub-group 1** (*W. Decking, H. Weise*)

Electron and Positron Sources  
(up to Damping Rings)

## **Sub-group 2** (*J. Rogers*)

Damping Rings

## **Sub-group 3** (*D. Schulte & P. Tenenbaum*)

Low Emittance Transport  
(from Damping Rings to IP)

## **Sub-group 4** (*W. Kozanecki*)

Machine Detector Interface

## **Sub-group 5** (*N. Phinney*)

Reliability and Availability

# Ground Motion Models

---


3 models used for simulations

A - quiet

B - medium

C - noisy

Based on data from various accelerators



## **Machine Tuning Simulations Sequence**

1. Start with a perfect machine and calculate luminosity
2. Introduce errors likely to exist upon installation
3. Make corrections using Beam Based Alignment (BBA) and Beam Bumps
4. Now include diluted input emittance, magnet jitter and ground motion assumptions along with energy jitter and changing klystron populations
5. Verify that beam-based feedbacks stabilize the beam and maintain luminosity over short-term
6. Repeat BBA and emittance tuning – verify that BBA and tuning algorithms converge in the presence of jitter (try to model realistic diagnostic performance)
7. Unfortunately, step 5 will take several months to complete; hence steps 4 and 6 must proceed in parallel on the basis of guessed assumptions for the effectiveness of the BBA and beam tuning



## **Machine Tuning Simulations Sequence**

1. Start with a perfect machine and calculate luminosity
2. Introduce errors likely to exist upon installation
3. Make corrections using Beam Based Alignment (BBA) and Beam Bumps
4. Now include diluted input emittance, magnet jitter and ground motion assumptions along with energy jitter and changing klystron populations
5. Verify that beam-based feedbacks stabilize the beam and maintain luminosity over short-term
6. Repeat BBA and emittance tuning – verify that BBA and tuning algorithms converge in the presence of jitter (try to model realistic diagnostic performance)
7. Unfortunately, step 5 will take several months to complete; hence steps 4 and 6 must proceed in parallel on the basis of guessed assumptions for the effectiveness of the BBA and beam tuning

## Conclusions

- Impressive technical inventions and discoveries are being made on all fronts
- But projects suffer from insufficient R&D funding, which seriously slows down indispensable experimental work
- TRC team work is outstanding although everybody is overextended and often sidetracked by internal lab deadlines, summer conferences and necessary vacations
- TRC “Process” is healthy in unifying accelerator community and will continue long after October 2002